

Thoroughbred Diesel Fasteners Heavy Duty Head Studs

Fits: Dodge 98.5-21 5.9L & 6.7L • Part Number: TDPFHSC9821

Parts Included: Tools Needed:
(26) Head Studs
(26) Head Stud Nuts
•Socket Set
•Torque Wrench

(26) Head Stud Washers

•Thread Chaser
(1) Assembly Lube


• M12 x 1.75

Please Read Instructions before starting installation. If you don't feel confident that you can complete this task, do not start it and seek professional help!

Note: It will be necessary to machine the lower rocker arm cover at the No.24 bolt hole location in the torque sequence to facilitate installation of the lower rocker arm cover. (see Illustrations)


cover. (see Illustrations)
☐ These instructions only cover the installation and torque sequence/technique of the Head Stud Kit.
☐ Clean and inspect the Studs, Washers, and Nuts to ensure they are free of shipping damage and obvious defects.
☐ Clean all threads in the block. It is recommended to use a Thread Chaser on the threads of the block so that they are completely clean to ensure proper thread engagement and accurate torque reading.
□ Lubricate the threads of the Head Studs and install them into the block. Be sure to only screw them in HAND TIGHT . Note: The longer (6.625") studs in this kit install along the exhaust manifold side of the cylinder head in the #3, #6, #11, #14, #19 and #22 position of the factory torque sequence. Look across the tops of the head studs to see that they all appear to be the same length. If one is taller, remove the stud, clean the threads in the block and re-install.
☐ Install the head gaskets and cylinder heads; check for any misalignment.
☐ Place head stud washers onto the head studs. Then lubricate the top of head stud washers and head stud threads with assembly lube.
☐ Lubricate the mating face and threads of the Head Stud Nuts with Assembly Lube.


- ☐ Snug all Head Stud Nuts on Studs, then follow the torque sequence below in a 3-step process.
 - 1. Tighten nuts 1 through 26 to 40 ft-lbs
 - 2. Tighten nuts 1 through 26 to 80 ft-lbs
 - 3. Tighten nuts 1 through 26 to 125 ft-lbs



• The amount of Head Stud threads showing above the Head Stud Nut should all be about the same. If one appears to have more thread, the stud is most likely not all the way in the head.

A: It will be necessary to machine the lower rocker arm cover at the #24 bolt hole location in the torque sequence to facilitate installation of the lower rocker arm cover.





B. Remove material as necessary to allow clearance for stud, nut and washer. Finish machine work should allow easy removal and installation of the head stud.

Disclaimer and Liabilities

Seller disclaims any responsibility/ liability for improper, incorrect, or inexperienced installation of products by the purchaser or installer resulting in damage or loss. Buyer affirms by purchase of this product that it is fit for intended use and accepts all liability. Buyer affirms products are used at buyers own risk and accepts full responsibility.



@THOROUGHBREDDIESEL

WWW.THOROUGHBREDDIESEL.COM